BRUHAT BANGALORE MAHANAGARA PALIKE

Dasarahalli Project Division

Draft Tender Schedule(DTS)

Name of work: Repairs to Chain link Fencing and SSM Wall at Shooting Building Road in Mallasandra ward No. 13

Sl No	Description of Work	Unit	Quantity as per Estimate	Sanctioned Rates in Rs	Rates Quoted by Contractor	
					In Figures	In Words
1	Earthwork excavation for foundation of buildings, water cum supply, sanitary lines and electrical conduits either in pits or in trenches1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m.after breaking of clods complete as per specifications as per Engineer incharge	cum	100.00	405.64		
2	Providing and laying in position plain cement concrete of cum mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. as per Engineer incharge	cum	15.00	5449.68		
3	Filling available excavated earth (excluding rock) in sides cum of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. as per	cum	50.00	137.16		
4	Providing and constructing granite I trap I basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of aterials, labour, scaffolding, curing complete as per as per Engineer incharge	Cum	56.00	6019.92		
5	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.as per Engineer incharge	Cum	145.71	5405.40		

No of concrete : NIL

No of carriage : NIL

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Scanned by CamScanner

	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 330kgs. with 20mm and down size graded granite metal coarse aggregates @0.64cum and fine aggregates @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.as per Engineer incharge	Cum	27.40	5966.36		
7	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materialscutting, bending scaffolding wherever necessary, nicely finishing the weldedjoints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) as per Engineer incharge	M	204.00	884.52		
8	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between / the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint. as per Engineer incharge	M	600.00	349.92		
9	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint as per Engineer incharge	Sqm	500.00	711.72		

No of corners : NIL

No of curves : NIL

ಸಹಾಯಕ ಅಧೀಕ್ಷಕರು
ಬೆಂಗಳೂರು ಮೇಖರಿಕ ವಲಯ
ಬಾಣಸವಾಡಿ ಪೊಲೀಸ್ ಠಾಣೆ, ಬೆಂಗಳೂರು

Scanned by CamScanner

	KSR 15.18.1 : Applying red lead ready mix priming coat over Sqm new steel or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and accured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications as per Engineer incharge	Sqm	1250.00	31.32		
11	KSR 15.18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. as per Engineer incharge	Sqm	1250.00	88.56		

Executive Engineer
Dasarahalli Project Division
BBMP - Bangalore

total no of coper NIL

total nc of overlay : NIL

" DTS APPROVED "

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸನಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Scanned by CamScanner